Dec 11, 1980

For HCRS use only · • •

received

date entered .

ŧ.

おい

. Ч 14

2/11/80

FHR-8-300	(11-78)
-----------	---------

### 'United States Department of the Interior **Heritage Conservation and Recreation Service**

## National Register of Historic Places Inventory-Nomination Form

See instructions in How to Complete National Register Forms Type all entries—complete applicable sections

1.	Name		A 44.2			<u> </u>
histor	ric Ferguson-C	Alerana Ho	ouse			
and o		rara House				
2.	Location					
street	<b>&amp; number</b> 2]4	N. 14th St.			not for	publication
city, t	own Fort Smith		vicinity of	congressional dis	trict Thir	d
state	Arkansas	code	05 cour	ty Sebastian	c	ode 131
3.	Classificat	ion				
	gory Ownership district public building(s) private structure both site Public Acqu object in proces being co	isition is nsidered	Status X occupied unoccupied work in progres Accessible X yes: restricted yes: unrestricted no	entertainme governmen	Ipar Ipriv entreli ttsci	vate residence gious entific nsportation
<b>L</b> ,	Owner of P	ropert	y			
name	• Mr. and Mrs.	Thomas Cal	derara			
-			enth Street			
city, t	town Fort Smith		<u> </u>		state Arkansas	5 72901
5.	Location o	f Legal	Descrip	tion		
court	house, registry of deeds, e	etc. Seb	astian County	Courthouse		
stree	t&number Rogers	Avenue an	d Sixth Street			
city, t	town Fort S	mith			<sub>state</sub> Arkansas	s 72901
6.	Representa	ation is	n Existing	g Surveys		
'itle				property been determi	ned elegible? _	<u>yes</u> no
date			,	federal	stateco	ounty local
depo	sitory for survey records					

### 7. Description

Condition	deteriorated	Check one	Check one
X excellent			_X_ original site
good	ruins	altered	moved date
fair	unexposed		

#### Describe the present and original (if known) physical appearance

The Ferguson-Calderara llouse is an irregularly massed structure that is two-and-one-half storys in height. The massing and detailing of the house are asymmetrical. The roof is a combination of gables and hips. Gable ends are located on the east, south, and north elevations. Two tall chimneys rise above the roof and each chimney is reinforced by an elaborate wrought-iron brace. A full basement is located beneath the house. Three porches are attached to the structure. A one-story porch spans all of the east (front) elevation and half of the soth elevation. Columns, linked by a balustrade, support the porch. An enclosed sleeping porch is situated on the southern half of the second story on the building's east elevation. A one-story porch enclosed with lattice-work is found on the west or rear elevation of the house.

Wood and stone were the primary materials used in the construction of the Ferguson-Calderrara House. Weatherboard sheaths the exterior. The edges of the exterior walls are defined by corner boards. The gable ends are shingled. A rusticated stone foundation supports the house.

A variety of window types are incorporated into the design of the house. Most windows are rectangular one-over-one double-hung. These windows vary in size and are asymmetrically arranged. Other window types include a Palladian window -n the gable end of the east elevation of the structure and an oculus on the first story of the south elevation. The most elaborate windows are those of the second story sleeping porch. The four windows of the sleeping porch form an arcade. Each window is a five-centered eliptical arch. A keystone punctuates each arch.

The entrance to the Ferguson-Calderara House is relatively simple. It is a single door embellished with an oval glazed-panel. The door is flanked by sidelights and is surmounted by a transom. The architrave is trabeated.

Most detailing utilized in the design of the house is classical. The one-story front porch possesses a full entablature sustained by unfluted columns with Ionic capitals. Ionic pilasters separate the windows of the second story sleeping porch. The house features a box cornice that is dentile. Carved garlands fill the extrados above the arches on the sleeping porch.

The balustrade of the one-story front porch features a distinctive handrail. The porch columns divide the balustrade into seven sections. The handrail in each section of the balustrade curves in a U-shape.

The interior of the house contains eleven rooms, five on the first floor and six on the second. The interior is elaborately detailed. Two rooms, the foyer and the front parlor, are located on the first floor. The foyer is dominated by a large brick fireplace. The fireplace features a corbelled breast and ornated mantel. The mantel line is articulated with curvilinear terra cotta relief work. The foyer walls are covered with linen that has been hand stenciled with flowers. The main staircase is located in the foyer. The staircase follows a dog-leg plan. The turned balusters and Form No. 10-300a (Hev. 10-74)

UNITED STATES DEPARTMENT OF THE INTERIOR			
NATIONAL PARK SERVICE			

				_
<b>FOA</b>	A10.0	LLOPE.	A	- 6 at 1
FOR	DUP	I I NE	11013	Y
			<b>U I I</b> I	L I

RECEIVED

DATE ENTERED

### NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

CONTINUATION SHEET	ITEM NUMBER	7 PAGE	1	
--------------------	-------------	--------	---	--


carved newel post are distinctive components of the staircase. A stained glass window overlooks the landing.

The walls are the outstanding element of the front parlor. They are divided into panels by bamboo-shaped strips. The wall covering is linen canvas that has been handpainted with oils. The design is a composition portraying books and roses.

Crossed oak beams are a part of the first floor ceilings. The beams possess a beaded trim. The original wood work found in architraves, baseboards, and other trimwork survives throughout the house.

h Te exterior of the Ferguson-Caldrara house retains its total integrity of appearance. The only significant alterations to the interior are those that accomodate modern plumbing, electrical and kitchen conveniences.

## 8. Significance



.

Statement of Significance (in one paragraph)

The Ferguson-Calderara House is significant both architecturally and historically. Classical detailing, irregular proportions and a wide variety of construction materials combine to make the structure an excellent example of Neo-Colonial Revival architecture. Both the exterior and interior of the house are little altered and are well-preserved. The historical significance of the home rests largely in the buildings association with Pine Bluff's commercial history. The lumber industry and the closely related furniture industry have long been two bulwarks of the Pine Bluff economy. A. L. Ferguson, for whom the house was built, was a pioneer and central figure in the Fort Smith lumber industry. Ferguson owned and operated the Ferguson Lumber Company, one of the largest lumber companies in the city.

# 9. Major Bibliographical References

Calderara, Thomas. Interview, April 1 Yadon, Julia. <u>Reflections of Fort Smit</u> Historical Press, 1976 Zanders, Betty. <u>Southwest Times Record</u>	<u>h</u> . Fort Smith, Arkansas: Fort Smith			
10. Geographical Data				
Acreage of nominated property <u>Less than one acre.</u> Quadrangle name <u>Ft. Smith, Ar</u> k./Okla. UMT References	Quadrangle scale 1:24,000			
A 115 371320 31916300 Zone Easting Northing	B Image: Second sec			
	D           F           H			
Verbal boundary description and justification				
Lots 11 and 12, block 16, Fitzgerald Ad	dition.			
List all states and counties for properties overlapping	state or county boundaries			
state code cou	inty code			
state code cou	inty code			
11. Form Prepared By				
name/title Mike Shinn, Historian. Historica	l Research: Julia Yadon and Bernice Cole			
organization Arkansas Historic Preservation Pro	gram date June 11, 1979			
street & number Suite 500, Continental Building	telephone (501) 371-2763			
city or town Little Rock	state Arkansas 72201			
	ation Officer Certification			
The evaluated significance of this property within the state is:				
As the designated State Historic Preservation Officer for the N 665), I hereby nominate this property for inclusion in the Natic according to the criteria and procedures set forth by the Herit	lational Historic Preservation Act of 1966 (Public Law 89– mal Register and certify that it has been evaluated			
State Historic Preservation Officer signature				
title State Historic Preservation Officer date June 11, 1979				
For HCRS use only I hereby certify that this property is included in the Natio	onal Register			
	date 1			
Keeper of the National Register				
Attest:	date			
Chief of Registration				

• 2-3

